## HASSAN DIVISION.

*The 13th October* 1903.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 20th November 1903; for restoring Kittenkere Tank, Registered No. 1094, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A.M. & 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kittenkere Tank, Registered No. 1094, Hassan," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of quantities for Restoring Kittenkere Tank, Registered No. 1094, Hassan Taluk.

| *Items of work.* | *Per* | *Quantity.* | *Rate.* |
|---|---|---|---|
| Bund— | | | |
| Earthwork ... ... ... ... | C. yd. | 21,492 | |
| Excavation and earthwork ... ... ... | C. yd. | 161 | |
| Turfing ... ... ... ... | S. yd. | 18,505 | |
| Old stone work ... ... ... ... | C. yd. | 164 | |
| New stone work ... ... ... ... | C. yd. | 1,099 | |
| Gravel backing to new revetment ... ... ... | C. yd. | 814 | |
| Jelly wedging to old do ... ... ... | C. yd. | 250 | |
| Grade stones with bed slab ... ... ... | Each. | 43 | |
| Vis-a-vis stone ... ... ... ... | Each. | 43 | |
| Register No. stone ... ... ... ... | Each. | 1 | |
| Date stone ... ... ... ... | Each. | 1 | |
| Gauge stone ... ... ... ... | Each. | 2 | |
| B. M. Stone ... ... ... ... | Each. | 2 | |
| Jungle clearing ... ... ... ... | L. S. | | |
| Left sluice— | | | |
| Excavation ... ... ... ... | C. yd. | 23 | |
| Burnt brick in surki mortar ... ... ... | C. ft. | 841 | |
| Burnt stone slabs ... ... ... ... | S. ft. | 43 | |
| Plastering with surki mortar ... ... ... | Sqr. | 3·44 | |
| Right sluice— | | | |
| Excavation ... ... ... ... | C. yd. | 16 | |
| Burnt brick in surki mortar ... ... ... | C. ft. | 489 | |
| Burnt stone slabs ... ... ... ... | S. ft. | 18 | |
| Plastering with surki mortar ... ... ... | Sqr. | 4·84 | |
| Waste-weir—Left— | | | |
| Clearing drafts and foundation ... ... ... | C. yd. | 1,100 | |
| Brick in surki mortar ... ... ... ... | C. ft. | 1,341 | |
| Burnt stone slabs ... ... ... ... | S. ft. | 246 | |
| Plastering with surki mortar ... ... ... | Sqr. | 5·24 | |
| Rough stone work new ... ... ... | C. yd. | 299 | |
| Right— | | | |
| Excavation ... ... ... ... | C. yd. | 48 | |
| Rough stone work, new ... ... ... | C. yd. | 51 | |

| *Items of work.* | *Per* | *Quantity.* | *Rate.* |
|---|---|---|---|
| Lifting Dam— | | | |
| Excavation ... ... ... | C. yd. | 75 | |
| Brick in surki mortar ... ... ... ... | C. ft. | 1,235 | |
| Plastering with surki mortar ... ... ... | Sqr. | 2·50 | |
| Burnt stone slabs ... ... ... ... | S. ft. | 168 | |
| Rough stone work, new... ... ... ... | C. yd. | 150 | |
| Jelly filling under apron ... ... .. | C. yd. | 42 | |
| Sluice Channel— | | | |
| Excavating right and left sluice channel ... ... | C. yd. | 138 | |
| Miscellaneous— | | | |
| Compensation for submerged dry lands under bed ... | Ac. | 2·25 | |

C. A. MAHADEVA SASTRI, *Executive Engineer.*

---

*Notice dated 14th October 1903.*

Notice is hereby given that a sum of Rs. 149-5-4 due to the undermentioned individuals on account of compensation for lands, etc., taken up for Hessarghatta Water Project, has been outstanding in the accounts, owing to the refusal of the first individual to receive the same and to the absence of the latter two whose whereabouts are unknown. If the claimants do not appear to receive payment within three months from this date, before the undersigned, the amounts will be credited to Government:—

| | Rs. | a. | p. |
|---|---|---|---|
| 1. Jodi Aivarakandapura, Nelamangala Taluk, Vanamala Vritti, original Inamdar Rama Pandit, mortgagee Mutkur Seenappa and Narasa Pandit ... ... ... ... ... | 12 | 0 | 0 |
| 2. Personal Inam belonging to Kristachar of Gondihalli, Dodballapur Taluk, ½rd share, Inamdar's whereabouts unknown ... | 71 | 5 | 4 |
| 3. Amount due to Munivenkata of Chikdevanapur, Dodballapur Taluk, on account of well and tamarind tree, the owner's whereabouts are unknown ... ... ... ... ... | 66 | 0 | 0 |
| Total ... | 149 | 5 | 4 |

B. J. KUMARASWAMI NAIK,
*Asst. Commissioner, Bangalore Range.*

---

## SEASON REPORT OF THE BANGALORE DISTRICT FOR THE MONTH OF AUGUST 1903.

*Rainfall.*—The average rainfall was 6 inches and 4·2 cents in the district during the month.

*State of the Crops.*—The standing crops are reported to be in good condition. Paddy, ragi, sorghum vulgare, castor, beans, pigeon-pea, panicum milliare, wild gingelly, and horse and cow gram were sown and sagar cane and Vysaki paddy harvested in parts of the District.

*Public Health.*—Good generally.

*Mortality.*—There were 924 deaths in the month of June against 947 in the month preceding.

*Cattle.*—1,895 head of cattle died during the month; of which 288 were killed by wild beasts.

*Lands.*—Lands assessed at Rs. 1,808-8-0 were taken up for cultivation.

H. H. SPARKES, *Dy. Comr.*

---

## GOVERNMENT CENTRAL BOOK DEPOT, BANGALORE.

*Notice dated 7th October 1903.*

It is hereby notified for information that copies of outline maps of Europe, World, Asia, England & Wales, Scotland and India, (published by Messrs. Longmans, Green & Co.), are available for sale.

The price of a copy of each is 4 pies.

S. ABDUL HAI, *Curator.*